#### GRUPO ASERCOM, S.A. DE C.V.

División Telecomunicaciones



To:

BREMBO MEXICO, S.A. DE C.V.

Attention to: Héctor Ramirez

Expiration day: 15 days
Terms of Payment: Cash

Date:

May 30 2015 Delivery Time: 1 Weeks

Agent: Ing. Edgar Robles

In response to your kind request put to it the following quote for the project:

#### RELOCATION OF AP

Cant	Description	Part No.	P.u. Material	P.u. Manpower	Total	
	NEW BUILDING					
155	Enhanced, Category 6, CM, 4-pair, UTP copper cable. Copper conductors are 24 AWG with polyethylene insulation. Conductors are twisted in pairs, and all four pairs are protected by a PVC jacket. Color blue	PUC6004BU	0.89	0.35	192.20	
3	Mini-Com ™ box for surface installation of two ports, supports up to two Mini-Com ™ modules. It includes an integrated module for adding a second removable empty module. Dimensions: 0.91 "high x 1.77" wide x 2.44 "long (23.1mm x 45.0mm x 62.0mm)	CBXJ2WH-A	3.50	3.80	21.90	
3	Category 6, UTP patch cord with TX6™ PLUS Modular Plugs on each end.	UTPSP7YL	10.20	0.80	33.00	
3	Category 6, UTP patch cord with TX6™ PLUS Modular Plugs on each end.	UTPSP3BU	8.80	0.80	28.80	
4	UTP Jack Module, Category 6, RJ45, 8-position, 8-wire universal module.	CJ688TGBU	10.40	3.20	54.40	
3	UTP Jack Module, Category 6, RJ45, 8-position, 8-wire universal module.	CJ688TGYL	10.40	3.20	40.80	
1	Plug RJ45	N/A	1.00	0.80	1.80	
3	Test, Node Identification and labeling N/A		2.80	2.40	15.60	
40	Thick Wall Pipe Conduit de 3/4"	N/A	9.48 3.79 53		530.80	
20	Coupling Thick Wall Conduit de 3/4"	N/A	0.54	0.22	15.20	
10	Locking and Monitor Thick Wall Conduit de 3/4"	g and Monitor Thick Wall Conduit de 3/4" N/A 0.28		0.18	4.60	
80	Conduit Pipe Support	N/A	8.20	8.20 6.20 1,152.00		
6	Elbow Wall Pipe Conduit de 3/4"	N/A	2.80	1.85 27.90		
4	Box 4 "x4"	N/A	3.50	1.80	1.80 21.20	
1	Miscellaneous lot	N/A	18.50	13.50 32.00		
1	Work at height	N/A	-	- 380.00 380.00		
1	Car Lift Platform, articulated arm 45 FT (1 week)	N/A	1,050.00	-	1,050.00	
1	Moving Platform	N/A	98.00	-	98.00	
		Sub Total sin IVA	\$	\$ 3,700.20 USD		

## Note:

Cabinet installation with existing window in place

<u>X</u>	USD	THE PRICES QUOTED IN THE ATTACHED ARE PRICED AS USD AND PAID AS SUCH. THEY DO NOT INCLUDE TAXES.	
	MN	THE PRICES QUOTED IN THE ATTACHED ARE PRICED IN THE NATIONAL MONEY AND DOES NOT INCLUDE TAXES.	

### Grupo Asercom, S.A. de C.V.

**Corporativo Monterrey** 

Joaquín García No. 215, Burócratas del Edo Monterrey, N.L. C.P. 64380 Conmutador (81) 1442-4000

# www.grupoasercom.com Sucursal Guadalaiara

Av. Circunvalación Agustín Yáñez No. 2360 Int 4-A Col. Arcos Sur Guadalajara, Jal. C.P. 44150 Tels (33) 3630-5030 y 3630-5033

### Sucursal México, D.F.

Río Lerma No. 26 Col. Cuauhtémoc Del. Cuauhtémoc México, D.F. C.P. 06500 Tels (55) 5703-0028 y 5703-0141